



Floor Plan  
6 1/2" & 8 1/4" Panels      3/16" = 1'-0"

PREMIER PANEL SHEAR WALL SCHEDULE

PANEL TYPE	OSB THICKNESS	ATTACHMENTS*				ANCHOR BOLT** SHEAR (kip)
		VERT. FRAMING	SPINES	BOTTOM PLATE	TOP PLATE	
L OR S	3/4"	8d @ 6" O.C., 2-ROWS	8d @ 6" O.C.	8d @ 6" O.C.	8d @ 6" O.C.	3/4" @ 48" O.C. 300

- NOTES:
1. FRAMING LUMBER SHALL BE MIN. DF-LARCH W/ SC-Q-SO
  2. DOUBLE STUD OR MINIMUM 4x FRAMING MEMBER IS REQUIRED
  3. TWO TOP PLATES REQUIRED
  4. BOLTS TO HAVE 3/4"x3"x3" WASHERS
  5. ANCHOR BOLTS TO HAVE MIN. 7" EMBEDMENT
  6. 8d-25 x0.131", 12d-32x0.131"
  7. 3x BOTTOM PLATE REQUIRED



**PREMIER**  
BUILDING SYSTEMS  
A CH2M HILL COMPANY

270 RIOS PLAT  
SUITE 200  
BELLEVUE, UT 84714  
405-306-5553

REVISIONS:		
#	CHANGER	DATE
1.	Tom R	12/1/05
2.	CHERT C	12/1/05
3.	CHERT C	12/1/05
4.	CHERT C	12/1/05
5.	CHERT C	12/1/05

CUSTOMER APPROVAL:

☐ APPROVED WITH REVISIONS AS SHOWN IN RED

☐ APPROVED AS DRAWN

SIGN HERE PLEASE

SIGNATURE

DATE

PROJECT INFORMATION

Cody Cattle Co.

Demaris St.

Cody, Wyoming

DATE

2 OF 6